

SECTION 01640
OWNER FURNISHED PRODUCTS

Foothill Middle School

PART 1 - GENERAL

1.1 **SUMMARY**

- A. **DESCRIPTION:** The Owner shall procure and provide certain products for installation as shown and specified per Contract Documents.
- B. **RELATED WORK SPECIFIED ELSEWHERE:**
 - 1. **General:** Products furnished and paid for by the Owner are described in the following technical sections and /or in the Drawings.
 - 2. **DISTRICT SUPPLIED MATERIAL**
Note that this project includes the installation of owner-supplied material; the District has acquired roofing material through the CMAS (California Multiple Award Schedules) program.

1.2 **DEFINITIONS**

- A. **GENERAL:** The following are used to identify products as noted on the Drawings.
- B. **OWNER FURNISHED CONTRACTOR INSTALLED (O.F.C.I.):** Products or equipment furnished by the Owner for installation under this contract.
- C. **OWNER FURNISHED OWNER INSTALLED (O.F.O.I.):** Products or equipment to be provided and installed by the Owner, but requiring surfacing, backing, utility connections or other preparation under this contract, for proper installation.
- D. **NOT IN CONTRACT (N.I.C.):** Products or equipment to be provided and installed by Owner, not requiring surfacing, backing, utility connections or other preparation under this contract.

PART 2 - PRODUCTS

2.1 **PRODUCTS**

- A. **ROOFING MATERIAL FURNISHED BY OWNER (O.F.C.I.):** District supplied material through the CMAS (California Multiple Award Schedules) program. Related specification sections include;
Section 075200 Modified Bituminous Membrane Roofing
Section 075630 Restoration for Mineral Surface BUR

B. MATERIAL LIST

- 23 - Flexbase 80. 1 sq roll.
- 32 - Stressply FR Mineral. 0.75 sq roll.
- 5- Flashing Bond Mastic, 5 gal pail
- 12 - Tuff Stuff Sealant 10.3oz Tubes
- 5 – White Star. 55 gal drum.
- 2 – White Star. 5 gal bucket
- 17 – All-Knight Primer. 5 gal bucket
- 2 – GarMesh 6” roll
- 6 - Pyramic Base Coat. 5 gal bucket
- 6 – Pyramic. 5 gal bucket

Any material or accessories required for the installation of the roof system in excess of the district provided material must be supplied by the Contractor. It is up to the Contractor to determine the precise amount of material required for the completion of this project; and to provide excess material, as required. The cost to handle and break flashing metal from the District provided flat stock is contractor's responsibility.

PART 3 - EXECUTION

2.2 OWNER'S RESPONSIBILITIES

- A. **SUBMITTALS:** Arrange for and deliver necessary shop drawings, product data and samples to Contractor.
- B. **DELIVERY:**
 - 1. **General:** Arrange and pay for product delivery to site, in accordance with construction schedule.
 - 2. **Bill of Materials:** Deliver supplier's documentation to Contractor.
 - 3. **Inspection:** Inspect jointly with Contractor.
 - 4. **Claims:** Submit for transportation damage and replacement of otherwise damaged, defective, or missing items.
- C. **GUARANTEES:** Arrange for manufacturer's warranties, bonds, service, inspections, as required.

2.3 CONTRACTOR'S RESPONSIBILITIES

- A. **SUBMITTALS:** Review shop drawings, product data and samples and submit to owner with notification of any discrepancies or problems anticipated in use of product.
- B. **DELIVERY:**
1. **General:** Designate delivery date for each product in Progress Schedule.
 2. **Receiving:** Receive and unload products at site. Handle products at site, including uncrating and storage.
 3. **Inspection:** Promptly inspect products jointly with Owner; record shortages, damaged or defective items.
 4. **Storage:** Protect products from damage or exposure to elements.
- C. **INSTALLATION:**
1. **General:** Assemble, install, connect, adjust and finish products, as stipulated in the respective section of Specifications.
 2. **Repair and Replacement:** Items damaged during handling and installation are responsibility of contractor.

* End Section 01640 *