



ATTENTION: MELANIE KOSLOW

PROJECT: TURF RESTORATION

CONTRACTOR: MDUSD

ESTIMATE: M445

DATE: 05-23-19

Location: 5120 Myrtle Dr. Concord, CA 94521

BOSCO CONSTRUCTION SERVICES, INC. WILL PROVIDE ALL MATERIALS AND LABOR REQUIRED AS PER THE SCOPE OF WORK FOR THE ABOVE MENTIONED PROJECT. THIS WORK WILL BE PERFORMED IN A PROFESSIONAL MANNER ACCORDING TO INDUSTRY STANDARDS.

DESCRIPTION: JUNE (PHASE 1)

GRADE AND LEVEL SOIL IN AREAS THAT ARE TOO HIGH OR LOW.

SPREAD EVENLY THE DIRT PILE ALREADY ON-SITE.

DEEP TINE AERATE THE FIELD WITH 3/4" SOLID TINES.

SEED THE FIELD WITH A HEAVY RATE OF BLUE/RYE MIX (500 LBS.).

TOP DRESS THE FIELD WITH 1/4" SAND/COMPOST MIX. (100 TONS).

APPLY A SEED STARTING FERTILIZER ACROSS THE FIELD (1LB. PER 1,000 SQ. FT.)

REVIEW THE IRRIGATION SYSTEM TO ENSURE PROPER WATERING COVERAGE AND REPAIRS ANY ISSUES AS NECESSARY.

PROVIDE A BROADLEAF WEED APPLICATION IN AUGUST TO HELP ELIMINATE CLOVER AND OTHER WEEDS.

TOTAL PRICE: **\$43,357.14**

EXCLUDES THE FOLLOWING: PERMIT OR INSPECTION FEES, ANY UNFORESEEN WORK/WORK NOT LISTED ABOVE IN DESCRIPTION.

BOSCO ASSUMES NO UNDERGROUND UTILITIES OR OTHER UNDERGROUND OBSTRUCTIONS ARE IN CONFLICT WITH THE WORK TO BE PERFORMED BY BOSCO OR ITS SUBCONTRACTORS. IF THERE ARE, OR THE CLIENT SUSPECTS THAT THERE MAY BE, THEY ARE TO BE LOCATED BY OTHERS PRIOR TO START OF WORK. BOSCO ASSUMES ALL IRRIGATION WIRES AND VALVES ARE AVAILABLE AND IN GOOD, OPERATING CONDITION AND CAN ACCOMMODATE THE ABOVE ENHANCEMENTS. THIS INCLUDES NEW AND MODIFIED IRRIGATION. BOSCO IS NOT RESPONSIBLE FOR DAMAGE TO UNDERGROUND UTILITIES NOT LOCATED PRIOR TO THE START OF WORK, BACKFLOW PREVENTER UNIT, DRAINAGE SYSTEM INSTALLATION, VIABILITY OF TRANSPLANTED PLANTS, REPAIR OF DAMAGED HARDSCAPE BEYOND OUR CONTROL, AND OTHER UNKNOWN ITEMS NOT SHOWN ON CLIENT-SUBMITTED, AS-BUILT DRAWINGS. LAYOUT, SUPERVISION AND QUALITY CONTROL MEASURES ARE INCLUDED.

MATTHEW CODIPILLY

MATTHEW CODIPILLY

PROJECT MANAGER

BOSCO CONSTRUCTION SERVICES, INC.

CELL 408-396-3870

05-23-2019

SIGN: _____

DATE: _____



ATTENTION: MELANIE KOSLOW
PROJECT: TURF RESTORATION (PHASE 2)
CONTRACTOR: MDUSD
ESTIMATE: M445
DATE: 05-23-19
Location: 5120 Myrtle Dr. Concord, CA 94521

BOSCO CONSTRUCTION SERVICES, INC. WILL PROVIDE ALL MATERIALS AND LABOR REQUIRED AS PER THE SCOPE OF WORK FOR THE ABOVE MENTIONED PROJECT. THIS WORK WILL BE PERFORMED IN A PROFESSIONAL MANNER ACCORDING TO INDUSTRY STANDARDS.

DESCRIPTION: OCTOBER (PHASE 2)
SEED THE FIELD WITH A STANDARD RATE OF BLUE/RYE MIX (250 LBS.).
TOP DRESS THE FIELD WITH 1/8" SAND/COMPOST MIX. (50 TONS).
APPLY A SEED STARTING FERTILIZER ACROSS THE FIELD (3/4 LB. PER 1,000 SQ. FT.)
REVIEW THE IRRIGATION SYSTEM TO ENSURE PROPER WATERING COVERAGE AND REPAIRS ANY ISSUES AS NECESSARY.
PROVIDE A BROADLEAF WEED APPLICATION IN NOVEMBER TO HELP ELIMINATE WEED GROWTH.

TOTAL PRICE: **\$28,642.86**

EXCLUDES THE FOLLOWING: PERMIT OR INSPECTION FEES, ANY UNFORESEEN WORK/WORK NOT LISTED ABOVE IN DESCRIPTION.
BOSCO ASSUMES NO UNDERGROUND UTILITIES OR OTHER UNDERGROUND OBSTRUCTIONS ARE IN CONFLICT WITH THE WORK TO BE PERFORMED BY BOSCO OR ITS SUBCONTRACTORS. IF THERE ARE, OR THE CLIENT SUSPECTS THAT THERE MAY BE, THEY ARE TO BE LOCATED BY OTHERS PRIOR TO START OF WORK. BOSCO ASSUMES ALL IRRIGATION WIRES AND VALVES ARE AVAILABLE AND IN GOOD, OPERATING CONDITION AND CAN ACCOMMODATE THE ABOVE ENHANCEMENTS. THIS INCLUDES NEW AND MODIFIED IRRIGATION. BOSCO IS NOT RESPONSIBLE FOR DAMAGE TO UNDERGROUND UTILITIES NOT LOCATED PRIOR TO THE START OF WORK, BACKFLOW PREVENTER UNIT, DRAINAGE SYSTEM INSTALLATION, VIABILITY OF TRANSPLANTED PLANTS, REPAIR OF DAMAGED HARDSCAPE BEYOND OUR CONTROL, AND OTHER UNKNOWN ITEMS NOT SHOWN ON CLIENT-SUBMITTED, AS-BUILT DRAWINGS. LAYOUT, SUPERVISION AND QUALITY CONTROL MEASURES ARE INCLUDED.

MATTHEW CODIPILLY

MATTHEW CODIPILLY
PROJECT MANAGER
BOSCO CONSTRUCTION SERVICES, INC.
CELL 408-396-3870

05-23-2019

SIGN: _____

DATE: _____

ALL QUOTED PRICING IS ONLY VALID FOR 90 DAYS AFTER ISSUANCE