



SHEET NOTES

- NOTES:
1. PROVIDE CONCRETE PULLBOX COMPLETE WITH EXTENSION AND COVER, MARKED LID "ELECTRICAL". PRODUCT AS MANUFACTURED BY CHRISTY OR APPROVED EQUAL.
 2. COORDINATE EXACT ROUTING OF DUCTBANK IN THE FIELD.
 3. THE CONTRACTOR SHALL BE RESPONSIBLE TO INVESTIGATE AND VERIFY THE ACTUAL LOCATION AND DEPTH OF ALL EXISTING UNDERGROUND FACILITIES AT LEAST 48 HOURS IN ADVANCE OF THE PERFORMANCE OF ANY WORK. CALL (USA) UNDERGROUND SERVICE ALERT. TEL#: 800-227-2600 BEFORE TRENCHING.
 4. CONTRACTOR TO BE COGNIZANT OF (H.V.) UG UTILITY LINE PRIOR TO EXCAVATION. COORDINATE WITH UTILITY CO AS NECESSARY PRIOR TO TRENCHING.
 5. REPAIR TRENCH LINE TO MATCH (E) SURFACE, TYP. UON.
 6. CONFIRM CONDUIT SIZE AND QUANTITY WITH DRAWING E3-XX.

KEY NOTES

- 1 PROVIDE CODE SIZE PULL BOX, SUITABLE FOR TRAFFIC LOADING, COMPLETED WITH EXTENSION AND STEEL COVER, COORDINATE EXACT LOCATION IN THE FIELD.
- 2 FOR ELECTRICAL SIGNAGE AND LOCATION SEE DWG. E11.
- 3 LOCATE AS DIRECTED BY SUNPOWER.

CONDUIT SCHEDULE

TAG	CONDUIT	FROM	TO
F1	(1) 3/4" C	CB "A1"	EQUIP PAD
F2	(1) 1-1/4" C	CB "A2"	EQUIP PAD
F3	(1) 1" C	CB "A3"	EQUIP PAD
F4	(1) 3/4" C	CB "A4"	EQUIP PAD
F5	(1) 1-1/2" C	CB "A5"	EQUIP PAD
F6	(1) 2" C	EQUIP PAD	TIE-IN LOCATION
F7	(1) 1" C	MET STATION	DAS

SUNPOWER

1414 HARBOUR WAY SOUTH - RICHMOND, CA 94804 USA
(510) 540-0560

ITEM	REVISIONS/ISSUE	DATE
1	DSA REVIEW	XX/XX/XX
	PG&E SUBMITTAL	10/12/11

ATI

ARCHITECTS
+
ENGINEERS

www.atiae.com
3860 Blackhawk Road
Danville, CA 94505
T 925.648.8900
2510 Douglas Boulevard
Roseville, CA 95661
T 916.772.1800
3050 Pullman Street
Costa Mesa, CA 92626
T 714.338.1600
1901 Orange Tree Lane
Foothill, CA 92374
T 909.801.8160

PROFESSIONAL STAMP:

REGISTERED ARCHITECT
MARK S. BELLO
C 20677
Exp: Mar. 31, 2013
STATE OF CALIFORNIA

REGISTERED PROFESSIONAL ENGINEER
PHIL IMMERMANN
E 10168
Exp: Dec. 31, 2011
STATE OF CALIFORNIA

APPROVALS:

PROJECT TITLE:
**SUNPOWER
ELEVATED
SOLAR CANOPY
HIDDEN VALLEY
ELEMENTARY
MT. DIABLO UNIFIED
SCHOOL DISTRICT**

SHEET TITLE:
**ELECTRICAL
SITE
PLAN**

DATE:
10/12/11

SCALE:
AS NOTED

DRAWN BY:
JAG/AR

CHECKED BY:
PMI

JOB NO:
SA8504.047

CAD FILE:
+E1_HV_Site.dwg

SHEET NO:

E1-HV